

CITY OF STOCKTON PUBLIC WORKS DEPARTMENT
FIRE STATION 2 COMMUNICATION CENTER UNINTERRUPTIBLE POWER
SUPPLY PROJECT, F022001
QUESTIONS and ANSWERS

Friday, January 14, 2022

1. The only 2 approved UPS manufacturers listed in specifications is Eaton and APL. Who is APL? And will alternate UPS manufacturers be acceptable, like Vertiv (formerly Liebert)

ANSWER: APL was a typo and should be APC. Vertiv is acceptable, other manufacturers should be submitted for pre-bid approval. This will be addressed in a Letter of Clarification.

2. There is NO UPS runtime requirement listed in the specs nor the plans. What is the UPS runtime requirement?

ANSWER: We are looking for a UPS that will provide 90 minutes of run time.

3. Does the existing UPS utilize a remote EPO switch or panel? Is one required for the new UPS installation?

ANSWER: The existing UPS has a front mount EPO and feeds an external panel.

4. The plans do not show the routing of the new utility feed from main switchgear to the new UPS. Will this be routed on the exterior of the building similar to panel "K"?

ANSWER: The feeder can run with the panel K feeder or through the attic.

5. Will Panel "K" and the new communications equipment receptacles that were installed remain in place once all new equipment is installed and operational?

ANSWER: Panel K can remain after the project is complete.

6. Will the cost of the City of Stockton building permit be the responsibility of the contractor or will the permit be issued at no charge?

ANSWER: The cost of the City of Stockton building permit will be the responsibility of the contractor.

7. What is the contractor's Insurance requirements for this project?

ANSWER: The insurance requirements can be found in the "INSTRUCTIONS TO BIDDERS" document posted on Bid Flash.