

No.	Street Name	Begin Location	End Location	Width (FT)	Length (FT)	Area (SF)	Area (SY)	Asphalt (TON)	Notes	Stop Bar (EA)	Stop Legend (EA)	Yield Line (LF) (EA)
1	3215 PACIFIC AV	Pacific Ave	220 West of Pacific Ave	36	220	7,920	880	150	S-Mart driveway on Alpine Ave - 36' x 220'		1	
2	6800 PACIFIC AV E FR RD	Benjamin Holt	Lincoln Rd	33	935	30,855	3,430	580	Recommend repaving street - 33' x 935' (Pacific Frontage from Benjamin Holt to Lincoln Rd)	2	2	
4	W ROBINHOOD DR & PACIFIC AV	Pacific Ave	Banbury	60	585	35,100	3,900	660	Recommend repaving street - 35,100 SF (Robinhood Dr from Pacific Av to Banbury)	2	2	
5	2232 E HAZELTON AV	S Mc Donell Ave	Court St	32	525	16,800	1,870	320	Recommend repaving street - 32' x 525'	1	1	
6	1800 LUCERNE AV	San Juan Ave	Buena Vista Ave	32	890	28,480	3,170	540	Recommend grind and pave - 32' x 890'	1	1	
7	2761 PACIFIC AV	Smith Ln and Pacific Ave							Install 15 x 36 concrete driveway			
8	9439 CHERBOURG WY	Morada Ln	Sandalwood Dr	36	1,750	63,000	7,000	1,190	Recommend repaving street -36' x 1,750' (Cherbourg Wy from Morada Ln to Sandalwood Dr)	6	6	
9	2317 W WILLOW ST	Dena Ct	Wilshire Ave	30	1250	37,500	4,170	710	30' x 1,250' grind and pave at 3"			

Total

219,655

24,420

4,150

Total	12	13	0
SQ Multiplier	264	286	12
White Thermoplastic	1613	ft²	

