



CITY OF STOCKTON

PUBLIC WORKS DEPARTMENT

MUNICIPAL SERVICE CENTER • 1465 S. Lincoln Street • Stockton, CA 95206-1941 • 209 / 937-8341 • Fax
209 / 937-8883

LETTER OF CLARIFICATION NO. 1

WEBER POINT EVENTS CENTER SHADE STRUCTURE REHABILITATION – PHASE 2 PROJECT NO. WP22033

TO ALL PROSPECTIVE BIDDERS

DATE: August 14, 2023

Letter of Clarification No. 1 for the above project consists of the following:

1. This acknowledgment form (see important Notice at the end of this document).

IMPROVEMENT PLANS:

2. Modification to the IMPROVEMENT PLANS sheet S3, "General Notes (Structural)":

- a. **REVISE** Note No. 1 under Cables.

1. Cables ~~EC1 & EC2~~ **E10, E11, E20, E21, E30, and E31** are new wire rope cables. All ~~remaining~~ **remaining** cables are to be existing cables, except in the event that damage is noted in the course of the work that would significantly impair the strength or durability of a cable. **New cables** ~~Cables EC1 - EC2 and any other replacement cables listed above~~ are to be fabricated in accordance with the requirements of these notes.

- b. **REVISE** Note No. 3 under Cables.

3. Cables **New cables** shall be wire rope conforming to ASTM A603, Class A, extra improved plow steel.

- c. **REVISE** Note No. 4 under Cables.

4. ~~Cables~~ **New cables** that are in direct contact with fabric shall be PVC sheathed, in white.

- d. **REVISE** Note No. 6 under Cables.

6. Cables **New cables** shall be prestretched to the designated load prior to fabrication.

e. **ADD** Note No. 9 under Cables.

9. Cable sheathing is required only on new 5/8" diameter "cat-eye" cables, not on existing cables. Sheathing shall be PVC, 90 durometers with UV inhibitors, and shall result in cables with smooth surface and 3/4" outside diameter.

3. Modification to the IMPROVEMENT PLANS sheet S6, "Installation Details":

REPLACE Cable Chart (6x19 Wire) with the following:

CABLE CHART (6X19 WIRE)			
MARK NO.	CABLE Ø (IN)	Prestretch Load (K)	Quantity
E10, E11, E20, E21, E30, E31	5/8	24	2

Notes:

1. Cables to be tensioned to prestretch load and released prior to fabrication.
2. Fabrication lengths and fabrication loads will be determined in the fabric patterning process.

SPECIAL PROVISIONS:

4. Page 19, Section 9-1.02, "QUANTITIES"

REVISE Base Bid Schedule Item No. 5 as follows:

Item	Description	Unit	Quantity	Unit Price	Total Price
5 (S)	Shade Structure Rehabilitation	LS	1		

(S) Denotes specialty item

BID FORMS:

5. Bid Forms: **REPLACE** with the revised Bid Forms dated 08/18/2023. Page 7 of 14 revised the Bidding Schedule, and the following changes were made:

Item	Description	Modification
5 (S)	Shade Structure Rehabilitation	Specialty Item denoted with (S)

QUESTIONS & ANSWERS:

6. Please review all Questions and Answers for this project.

“Bids not presented on the revised bid forms shall be cause for considering the bid as non-responsive.”

JODI ALMASSY, DIRECTOR
PUBLIC WORKS DEPARTMENT



CHAD REED, DEPUTY DIRECTOR
PUBLIC WORKS DEPARTMENT

JLA:CR:RA:TP:ASG:kt

NOTICE: THIS FORM MUST BE SIGNED AND RETURNED WITH YOUR BID. FAILURE TO INCLUDE OR ACKNOWLEDGE A CLARIFICATION MAY RESULT IN THE BID BEING REJECTED AS NOT RESPONSIVE.

CONTRACTOR: _____

CONTRACTOR SIGNATURE: _____

DATE: _____