



CITY OF STOCKTON

PUBLIC WORKS DEPARTMENT

22 East Weber Avenue, Room 301 • Stockton, CA 95202-2317 • 209 / 937-8411 • Fax 209 / 937-8277
www.stocktonca.gov

LETTER OF CLARIFICATION NO. 1

LIGHTED CROSSWALK UPGRADES PROJECT NO. WT15026

TO ALL PROSPECTIVE BIDDERS

DATE: October 20, 2022

Letter of Clarification No. 1 for the above project consists of the following:

1. This acknowledgement form (see important notice at the end of this document).

SPECIAL PROVISIONS:

2. SP27, Section 9-1.02, "Description of Work":

CHANGE the bid item to read

~~20. Hot Mix Asphalt Vehicular Asphalt Pavement (HMA 4" AC/ 12" AB)~~

- a. ~~By the ten square foot, verified by weigh slips from an approved weigh station.~~ Asphalt binder must be PG 64-10 or PG 70-10 and must comply with section 39-1.02 of Caltrans Standards Specifications. HMA for base and surface course paving shall be Type A, $\frac{3}{4}$ " maximum, medium aggregate. Includes compacting subgrade and placing aggregate base and constructing to the elevations, thickness, and locations, forming, reinforcing. Includes placing hot mix asphalt (leveling) supplying and placing asphalt binder, supplying, preparing, placing, grading the subgrade in preparation of the finished grade sections, as well as excavating and compacting asphalt concrete and constructing to the elevations, thickness and locations as indicated on the Plans described in these Special Provisions.

3. SP32, Section 9-1.02, "Description of Work"

INCLUDE the following bid item

57 2" Overlay (HMA)

- a. By the square foot. Asphalt binder must be PG 64-10 or PG 70-10 and must comply with section 39-1.02 of Caltrans Standards Specifications. HMA for base and surface course paving shall be Type A, $\frac{3}{4}$ " maximum, medium aggregate. Includes placing hot mix asphalt (leveling) supplying and placing asphalt binder, supplying, preparing, placing, grading the subgrade in preparation of the finished grade sections, as well as excavating and compacting asphalt concrete and constructing to the elevations, thickness and locations as indicated on the Plans described in these Special Provisions.



4. Page SP33, Section 9-1.03, "Quantities":

Revise bid schedule to read:

ITEM NO.	ITEM DESCRIPTION	UNITS	ESTIMATED QUANTITY
20	VEHICULAR ASPHALT PAVEMENT (HMA 4" AC /12" AB)	TON SF	60 -2,215
57	2" OVERLAY (HMA)	SF	3,060

BID FORMS:

5. Bid Forms: **REPLACE** with the revised Bid Forms dated 10-20-2022. The following items have been revised:

a. Page 4

ITEM NO.	ITEM DESCRIPTION	UNITS	ESTIMATED QUANTITY
20	VEHICULAR ASPHALT PAVEMENT (HMA 4" AC /12" AB)	TON SF	60 -2,215
57	2" OVERLAY (HMA)	SF	3,060

JODI ALMASSY, DIRECTOR
 PUBLIC WORKS DEPARTMENT



ERIC ALVAREZ, P.E.
 DEPUTY PW DIRECTOR/CITY ENGINEER

JLA:EA:DV:DY:JA:cal

NOTICE: THIS FORM MUST BE SIGNED AND RETURNED WITH YOUR BID. FAILURE TO INCLUDE OR ACKNOWLEDGE A CLARIFICATION MAY RESULT IN THE BID BEING REJECTED AS NOT RESPONSIVE.

CONTRACTOR: _____

BIDDER SIGNATURE: _____

DATE: _____