

CITY OF STOCKTON – PUBLIC WORKS DEPARTMENT

QUESTIONS-ANSWERS-CLARIFICATIONS

PACIFIC AVENUE AND MARCH LANE INTERSECTION MODIFICATIONS

PROJECT NO. WT17025, (FORMERLY PROJECT NO. PW1725)

FEDERAL PROJECT NO. CML-5008(181)

2/14/2023

Q1: Description for item 19 calls for 4" HMA. However, typical sections A & B on sheet C2.1 and Paving Legend table on sheet C4.0 call for 7" HMA. Please clarify which of these is correct?

A1: The item should be 7" HMA and not 4" HMA. This is a mistake on the bid form. It will be fixed via LOC #1.

Q2: Paving Legend table on sheet C4.0 calls for 17.5" Deep lift AC. Would this be paid under item 19?

A2: The 17.5" deep lift will be paid through Bid item #33 as detailed in the specification section 9-1.02. This will be considered asphalt restoration for the storm drainpipe installation. The legend on sheet C4.0 in the plans distinguishes what will be 17.5" asphalt deep lift and what will be 7" asphalt deep lift.

2/17/2023

Q1: Per sheet C3.0 states onsite improvements see plan by others? Are there plans forthcoming for this or is this a separate project outside of the scope of work for the project?

A1: You can ignore that note since the raising canes property is already built out. This was a separate project that was being developed during design of the project.

2/23/2023

Q1: I noticed last minute that line item #25 is doubled up on page 5 and 6, how would you like us to proceed?

A1: Please repeat your bid on this bid item and we will adjust during bid review.