

**QUESTIONS AND ANSWERS  
INSTALL LEFT-TURN SIGNALS AT THREE INTERSECTIONS  
CITY PROJECT NO. WT17026**

1. Question: Please clarify bid item 13 & 14?

**Answer:** The revised quantity for these bid items is 8 EA, corresponding to 8 APS push buttons total being installed throughout the project.

2. Question: Please clarify bid item 26? Is there additional HMA in other locations?

**Answer:** This bid item includes removing asphalt and concrete and aggregate base to account for roadway excavation. The quantity has been revised.

3. Question: Please clarify bid item 27?

**Answer:** This includes all concrete curb (vertical curb and gutter, retaining curb in ped passageways, roll type curb, etc.) and is quantified in LF.

4. Question: Please clarify bid item 29 is regular concrete, no stamp color or special Finish?

**Answer:** Correct. No stamp, color, or special finish required.

5. Question: Please confirm no reinforcement is required on the project as it is stated in the pay items for minor concrete but no detail provided?

**Answer:** Reinforcement is required for minor concrete items which includes bid items #27 - #30, and shall be done in accordance with City of Stockton Standard Plans, including, but not limited to, Drawing Nos. R50, R51, R52, R53, and R54.

6. Question: Please confirm where the 4 surface mounted domes on CD-01 are paid for?

**Answer:** The surface mounted domes shall be included under Bid Item 31, Detectable Warning Surface.