

CITY OF STOCKTON – PUBLIC WORKS DEPARTMENT
INSTALL LEFT-TURN LANES AT AIRPORT WAY AND HAZELTON AVENUE
CITY PROJECT NO. WT19002/FEDERAL PROJECT NO. HSIPL-5008(184)
QUESTIONS AND ANSWERS

Q1. Will the City allow Conductors (electrical wire) to be installed via the slip in method or will the City require full repulls of the intersection per Caltrans standards?

Ans: The City will require repull per Caltrans standards to make sure the existing wires will not be damaged with the slip in method.

Q2. The Demolition Plans call out to “Remove Pavement Section to 12” Depth”. There isn’t a bid item for this work, please confirm where or how this work is to be paid.

Ans: Removal of pavement is paid for under Bid Item 24, Hot Mix Asphalt (Type A).

Q3. The City Standard Details call out Class-2 AB under the curb ramps, sidewalk, curb & gutter, and the driveways. There isn’t a bid item for this work, please confirm where or how this work is to be paid.

Ans: The aggregate base for curb ramps, sidewalk, curb and gutter, and driveways shall be paid for under Bid Items 19 (Curb Ramps), 25 (Minor Concrete – Linear Foot), 26 (Minor Concrete - Curb and Gutter), 27 (Minor Concrete – Sidewalk), 28 (Minor Concrete – Cobbles Embedded in Concrete), 40 (Remove Concrete - Driveway), 41 (Residential Driveway Reconstruction) and 43 (Concrete Sidewalk – Adjacent to Bridge Type Driveway).

Q4. Section 5-1.08 of the Special Provisions requires the contractor to provide the Construction Staking on this project. There isn’t a bid item for this work, please confirm where or how this work is to be paid.

Ans: Refer to the payment clause under this section. This item is paid for by the various contract items.

Q5. Section 14-1.01 of the Special Provisions indicates that the Earth Material that will be excavated and disposed of from this project contains Aerially Deposited Lead. Please provide the test results that show what the existing concentrations of lead are for this material so that the contractor can determine how this material will need to be disposed of.

Ans: Section 14-1.01 contains requirements for the handling, testing, removing, and disposing of earth material containing lead. Contractor shall submit a lead compliance plan as required in the specifications.

Q6. Section 20-1.02 of the Special Provisions “Tree Removal and Pruning and Root Trimming”, requires the contractor to replace the trees that are removed as part of this contract with 15-gallon container size Ginkgo (Fairmount) trees. There are no other specifications on any planting requirement, irrigation requirements, root barrier, soil prep

and such. Please provide additional information for the replacement tree planting. In addition, there isn't a bid item for this work, please confirm where or how this work is to be paid.

Ans: There are no new trees to be replaced or planted under this contract.

Q7. Section 20-1.01 of the Special Provisions "Planting and Irrigation", requires the contractor to furnish and install 12" minimum of Imported Topsoil in planting areas. Please clarify and quantify where the Planting Areas are located or what the limits of those areas are. In addition, there isn't a bid item for this work, please confirm where or how this work is to be paid.

Ans: There are no new trees to be planted under this contract.