



CITY OF STOCKTON

PUBLIC WORKS DEPARTMENT
OPERATIONS AND MAINTENANCE

1465 S. Lincoln Street • Stockton, CA 95206-1941 • 209 / 937-8341 • Fax 209 / 937-8883
stocktonca.gov

LETTER OF CLARIFICATION NO. 2

**GRUPE PARK PARKING LOT RESURFACING,
PROJECT NO. WD22011**

TO ALL PROSPECTIVE BIDDERS

DATE: January 16, 2024

Letter of Clarification No. 2 for the above project consists of the following:

1. This acknowledgement form (see important Notice at the end of this document).

NOTICE TO CONTRACTORS:

2. The "Bid Opening Date" has been updated to the following:

**"January 25, 2024, 2:00 p.m."
City of Stockton
City Hall
City Clerk's Office
425 N. El Dorado Street, 1st Floor
Stockton, CA 95202**

SPECIAL PROVISIONS:

3. Page 35, Section 9-1.02, "PAYMENTS"

REVISE the following:

16. Unclog/Clean existing Storm Drain Inlet and Pipes

- a. By the unit. Includes providing all labor, materials, tools, equipment, to unclog all drain inlets **and pipes** within parking lot project limits and removing waste materials from the site and performing the work, and incidentals as indicated on the Plans and described in these Special Provisions.

4. Page 39, Section 9-1.02, "PAYMENTS"

REVISE the following:

37.3' Wide Asphalt ~~Rubber~~ Speed Bump

- a. By the unit. Includes providing all labor, materials, tools, equipment, and incidentals for installing asphalt ~~rubber~~ speed bumps as indicated on the Plans and described in these Special Provisions.

5. Page 39, Section 9-1.02, "PAYMENTS"

ADD the following:

38.6" Concrete Vertical Curb at Seagull Lane

- a. By the linear foot. Includes supplying concrete to the site, compacting subgrade and placing aggregate base and constructing to the elevations, thickness, and locations, forming, reinforcing, placing concrete, removing forms, curing, finishing, loading, grading the subgrade in preparation of the finished grade sections, as well as excavating and removing waste materials from the site, and constructing the facilities as indicated on the Plans and described in these Special Provisions.

6. Page 41-42, Section 9-1.06, "PAYMENTS"

REVISE the following:

ITEM NO.	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY
16	UNCLOG/CLEAN EXISTING STORM DRAIN INLET AND PIPES	EA	6
37	3' WIDE ASPHALT RUBBER SPEED BUMP	EA	2
38	6" CONCRETE VERTICAL CURB AT SEAGULL LANE	LF	25

IMPROVEMENT PLANS:

7. Modification to the IMPROVEMENT PLANS sheet 2, "GENERAL NOTES"

REVISE Striping and Signage Note No. 3:

- a. ~~ALL PAVEMENT MARKINGS, STRIPING AND CROSSWALKS SHALL BE THERMOPLASTIC~~ **ALL PAINT SHALL CONFORM TO SECTION 84-2.02G "PAINT" OF THE CALTRANS SPECIFICATIONS.**

BID FORMS:

8. BID FORMS: **REPLACE** with the revised Bid Forms dated 01/16/2024. Revised the Bidding Schedule on pages 4 and 5. The following changes were made:
- **REVISE** Bid Item #16: UNCLOG/CLEAN EXISTING STORM DRAIN INLET **AND PIPES**
 - **REVISE** Bid Item #37: 3' WIDE ASPHALT **RUBBER** SPEED BUMP
 - **ADD** Bid Item #38: 6" CONCRETE VERTICAL CURB AT SEAGULL LANE

QUESTIONS & ANSWERS:

9. Please review all Questions and Answers for this project.

“Bids not presented on the revised bid forms shall be cause for considering the bid as non-responsive.”



CHAD REED, INTERIM DIRECTOR
PUBLIC WORKS DEPARTMENT

CR:RA:TP:AG:kc

NOTICE: THIS FORM MUST BE SIGNED AND RETURNED WITH YOUR BID. FAILURE TO INCLUDE OR ACKNOWLEDGE A CLARIFICATION MAY RESULT IN THE BID BEING REJECTED AS NOT RESPONSIVE.

CONTRACTOR: _____

CONTRACTOR SIGNATURE: _____

DATE: _____