



CITY OF STOCKTON

PUBLIC WORKS DEPARTMENT

MUNICIPAL SERVICE CENTER • 1465 S. Lincoln Street • Stockton, CA 95206-1941 • 209 / 937-8341 • Fax
209 / 937-8883

LETTER OF CLARIFICATION NO. 2

LOCAL STREET RESURFACING PROGRAM FY 2023-24 SB1 – MILL AND OVERLAY PROJECT NO. WD24003D

TO ALL PROSPECTIVE BIDDERS

DATE: September 25, 2023

Letter of Clarification No. 1 for the above project consists of the following:

1. This acknowledgment form (see important Notice at the end of this document).

NOTICE TO CONTRACTORS:

2. The “Bid Opening Date” has been updated to the following:

“October 5, 2023, 2:00 P.M.”
City Hall, City Clerk’s Office
425 N. El Dorado Street, 1st Floor
Stockton, CA 95202

SPECIAL PROVISIONS:

3. Page 28, Section 9-1.02, “PAYMENTS”

ADD the following bid items:

13. Additional Concrete Sidewalk Removal and Replacement: paid per square foot. Includes saw cutting: removal and disposal of existing concrete and debris, cutting and removal of tree roots under the sidewalk, excavating existing base to install 6” thick concrete sidewalk and 4” thick compacted aggregate base, adjusting existing catch basin and pull box, installation of dowels, saw cutting of existing asphalt pavement and dirt to fit wood forms, and repair of damaged landscape and sprinkler due to the construction work. Work also includes backfilling, grading, and compacting material (95%) at back of sidewalk.

14. Additional Curb and Gutter Removal and Replacement: paid per linear foot. Includes saw cutting: removal and disposal of existing concrete and debris, cutting and removal of tree roots under the gutter, excavating existing base to install concrete, gutter, and compacted aggregate base per City Standard Specifications, installation of dowels, saw cutting and removal of existing asphalt pavement (1 foot from the gutter lip and 8 inches deep) and dirt to fit wood forms, and repair of damaged landscape and sprinkler due to the construction work.

15. Speed Hump Removal and Replacement: paid per each. Includes removal and disposal of existing speed hump, installation of speed hump on new pavement, complete in place, as indicated in these special provision, specified in the Standard Plans and Specifications, and as directed by the Engineer, and no additional compensation will be allowed.

4. Page 30, Section 9-1.06, "QUANTITIES"

ADD the following bid items:

ITEM NO.	DESCRIPTION	UNIT	ESTIMATED QUANTITY
24	Additional Concrete Sidewalk Removal and Replacement	SF	400
25	Additional Curb and Gutter Removal and Replacement	LF	200
26	Speed Hump Removal and Replacement	EA	4

BID FORMS:

5. Bid Forms: **REPLACE** with the revised Bid Forms dated 9/25/2023. Page 5 of 13 revised the Bidding Schedule, and the following changes were made:

Item	Description	Unit	Quantity	Unit Price	Total Price
24	Additional Concrete Sidewalk Removal and Replacement	SF	400		
25	Additional Curb and Gutter Removal and Replacement	LF	200		
26	Speed Hump Removal and Replacement	EA	4		

PROJECT MAP:

6. **REPLACE** with the revised Project Map dated 9/25/2023. The location of Lucerne Av from San Juan Av to Buena Vista Av was removed from the project map.

CURB RAMP LOCATIONS:

7. **ADD** Curb Ramp Locations as an Attachment.

STREET LIST AND QUANTITY:

8. **REPLACE** with the revised Street List and Quantity dated 9/25/2023.

QUESTIONS & ANSWERS:

9. Please review all Questions and Answers for this project.

“Bids not presented on the revised bid forms shall be cause for considering the bid as non-responsive.”

JODI ALMASSY, DIRECTOR
PUBLIC WORKS DEPARTMENT



CHAD REED, DEPUTY DIRECTOR
PUBLIC WORKS DEPARTMENT

JLA:CR:RA:TP:kt

NOTICE: THIS FORM MUST BE SIGNED AND RETURNED WITH YOUR BID. FAILURE TO INCLUDE OR ACKNOWLEDGE A CLARIFICATION MAY RESULT IN THE BID BEING REJECTED AS NOT RESPONSIVE.

CONTRACTOR: _____

CONTRACTOR SIGNATURE: _____

DATE: _____